COMMUNITY DEVELOPMENT PERMIT CENTER



FASTENING SCHEDULE (B22)

2016 CA. RESIDENTIAL CODE R602.3(1)

TABLE R602.3(1) FASTENING SCHEDULE

ITEM	DESCRIPTION OF BUILDING ELEMENTS	NUMBER AND TYPE OF FASTENER®, D, C	SPACING AND LOCATION
		Roof	
1	Blocking between ceiling joists or rafters to top plate	4-8d box $(2^{1}/_{2}" \times 0.113")$ or 3-8d common $(2^{1}/_{2}" \times 0.131")$; or 3-10d box $(3" \times 0.128")$; or 3-3" $\times 0.131"$ nails	Toe nail
2	Ceiling joists to top plate	4-8d box $(2^{1}/_{2}" \times 0.113")$; or 3-8d common $(2^{1}/_{2}" \times 0.131")$; or 3-10d box $(3" \times 0.128")$; or 3-3" $\times 0.131"$ nails	Per joist, toe nail
3	Ceiling joist not attached to parallel rafter, laps over partitions [see Sections R802.3.1, R802.3.2 and Table R802.5.1(9)]	4-10d box (3"×0.128"); or 3-16d common (3 ¹ / ₂ "×0.162"); or 4-3"×0.131" nails	Face nail
4	Ceiling joist attached to parallel rafter (heel joint) [see Sections R802.3.1 and R802.3.2 and Table R802.5.1(9)]	Table R802.5.1(9)	Face nail
5	Collar tie to rafter, face nail or $1^{1}/_{4}$ " \times 20 ga. ridge strap to rafter	4-10d box (3" × 0.128"); or 3-10d common (3" × 0.148"); or 4-3" × 0.131" nails	Face nail each rafter
6	Rafter or roof truss to plate	3-16d box nails (3 ¹ / ₂ "×0.135"); or 3-10d common nails (3"×0.148"); or 4-10d box (3"×0.128"); or 4-3"×0.131" nails	2 toe nails on one side and 1 toe nai on opposite side of each rafter or truss'
7	Roof rafters to ridge, valley or hip rafters or roof rafter to minimum 2" ridge beam	4-16d (3 ¹ / ₂ " × 0.135"); or 3-10d common (3 ¹ / ₂ " × 0.148"); or 4-10d box (3" × 0.128"); or 4-3" × 0.131" nails	Toe nail
,		3-16d box 3 ¹ / ₂ " × 0.135"); or 2-16d common (3 ¹ / ₂ " × 0.162"); or 3-10d box (3" × 0.128"); or 3-3" × 0.131" nails	End nail
		Wall	
	Stud to stud (not at braced wall panels)	16d common (3 ¹ / ₂ " × 0.162")	24" o.c. face nail
8		10d box (3" × 0.128"); or 3" × 0.131" nails	16" o.c. face nail
9	Stud to stud and abutting studs at intersecting wall corners (at braced wall panels)	16d box (3 ¹ / ₂ " × 0.135"); or 3" × 0.131" nails	12" o.c. face nail
		16d common (3 ¹ / ₂ " × 0.162")	16" o.c. face nail
10	Built-up header (2" to 2" header with 1/2" spacer)	16d common $(3^1/_2" \times 0.162")$	16" o.c. each edge face nail
		16d box (3 ¹ / ₂ " × 0.135")	12" o.c. each edge face nail
11	Continuous header to stud	5-8d box (2 ¹ / ₂ " × 0.113"); or 4-8d common (2 ¹ / ₂ " × 0.131"); or 4-10d box (3" × 0.128")	Toe nail
12	Top plate to top plate	16d common (3 ¹ / ₂ " × 0.162")	16" o.c. face nail
		10d box (3" × 0.128"); or 3" × 0.131" nails	12" o.c. face nail
13	Double top plate splice for SDCs A-D ₂ with seismic braced wall line spacing < 25'	8-16d common (3 ¹ / ₂ " × 0.162"); or 12-16d box (3 ¹ / ₂ " × 0.135"); or 12-10d box (3" × 0.128"); or 12-3" × 0.131" nails	Face nail on each side of end joint (minimum 24" lap splice length each side of end joint)
	Double top plate splice SDCs D_0 , D_1 , or D_2 ; and braced wall line spacing $\geq 25'$	12-16d (3 ¹ / ₂ " × 0.135")	